663

MYSORE DIVISION.

Dated 8th January 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, upto 8th February 1919, for improving the 2nd class tavellers' bungalow at Mandya. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the 2nd class travellers' bungalow at Mandya, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineeer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for improving 2nd class travellers' bungalow at Mandya.

Items of work	Main building		Native kitchen	European kitchen	Stables	Motor shed	Motor pit	New latrine	Total
	Per	Quantity							
Main.									
Dismantling existing Bengal terrace and re-roofing with 1st class Mangalore roofing tiles set in mortar over the existing reepers and a course of flat tiles.	Sq.	31·50	...	...	...	...	...	...	31·50
Mangalore ridge tiles set in mortar	R. ft.	68	...	46	...	...	...	...	114
Burnt brick in surki mortar	C. ft.	...	...	...	...	...	...	479	479
Brick in chunam	"	90	...	...	...	353	...	...	443
Burnt stone in chunam	"	...	...	...	...	...	129	...	129
Chunam plastering	Sq.	1·75	...	...	...	4·99	·63	6·66	14·03
Burnt stone slabs dressed and fixed ...	S. ft.	46	...	...	...	54	59	6	165
Removing window and fixing door	L. S.	1	...	...	...	...	...	...	1
Teakwood ventilators with iron bars and glazed shutters, etc.	S. ft.	7	...	...	...	9	...	...	16
Painting	Sq.	2·46	...	...	...	...	...	...	2·46
Wood oiling	"	...	...	...	...	L.S.	...	...	L.S.
Flooring with 1st class square tiles on 3" concrete bed and cement pointed.	"	1·44	2·82	...	...	...	...	...	42·6
Flooring with Cudappah slabs	"	...	1·40	...	...	...	...	...	1·40
Teakwood panelled door, complete ...	S. ft.	91	...	...	...	...	...	...	91
Do teakwood wrought and put up	C. ft.	16	...	...	...	...	...	...	16
Jungle wood wrought and put up including tarring ...	"	...	...	...	...	...	...	11·62	11·62
Stone brackets including cutting and fixing ...	No.	14	...	...	...	...	...	...	14
Mending the sugged rafters and refixing	L. S.	...	...	...	...	...	...	...	L.S.
Removing existing plastering	Sq.	...	2·82	...	...	...	...	...	2·82
Providing wooden pegs including nails	No.	...	12	...	...	...	...	...	12
Lever locks	"	...	1	...	...	...	...	...	1
Ventilating tiles	"	...	4	...	...	...	...	...	4
Constructing sinks in bath rooms		...	L.S.	...	...	...	...	...	L.S.
Do surki in concrete drain	R. ft.	...	50	...	...	...	...	...	50
Providing wire gauze	S. ft.	...	6	...	...	...	...	...	6
Removing old roofing and stacking ...	"	...	...	12·88	12·88	...	...	1·10	26·86
Roofing with 1st class Mangalore tiles on teakwood reepers, etc., complete.	"	...	...	12·88	12·88	...	...	1·12	26·88
Providing iron bars $\frac{3}{4}$" dia. to windows	R. ft.	...	...	95	...	...	...	...	95
Dismantling the masonry and removing debries outside the compound.	C. ft.	...	...	...	...	111	...	603	714
Excavation of earthwork	C. yd.	...	...	...	...	3	...	...	3
White and colourwashing	Sq.	...	...	...	...	L.S.	...	L.S.	L.S.
Teakwood frame with zinc shut iron works, etc. ...	S. ft.	...	...	...	...	90	...	...	90
Bund stone	No.	...	...	...	...	6	...	7	13
Opening new road for motor shed	L. S.	...	...	...	...	L.S.		...	L.S.
Chunam concrete	C. ft.	...	...	...	...	...	...	22	22
Cement plastering $\frac{1}{4}$" thick	Sq.	...	...	...	...	...	...	2·00	2·00
Coping 9" thick for walls including plastering, etc. ...	R. ft.	...	...	...	...	...	...	15	15
Mortor bunds 9" thick over roofing	"	...	...	...	...	...	...	33½	33½
Tarring	...	...	...	...	...	...	...	L.S.	L.S.
Fixing Mangalore tiles for seats	No.	...	...	...	...	...	...	16	16
Fixng pipes 3" dia.	R. ft.	...	...	...	...	...	...	2	2
Fixing a teakwood wicket gate for entrance with hinges padlocks, etc.	S. ft.	...	...	...	...	...	...	10	10

Camp Nelligere, dated 16th January 1919. 664

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 20th February 1919, for constructing a bridge of 4 arches of 35' span at $\frac{7}{8}$ of Bangalore-Mangalore road, *via* Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1921.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a bridge in $\frac{7}{8}$ of Bangalore-Mangalore road, *via* Hassan," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a bridge of 4 arches of 35 feet span in continuation of the single arched one at $\frac{7}{8}$ mile of Bangalore-Mangalore road, *via* Hassan. (Running in Krishnarajpete Taluk).

Sl. No.	Items of work	Per	Quantity
	Bridge.		
1	Earthwork excavation for foundation	C. yd.	778
2	Earthwork draft and approach clearing	"	43,997
3	Surki concrete foundation	C. ft.	1,124
4	Stone in surki mortar	"	23,536
5	Do arch work	"	4,200
6	Centering charges	L. S.	...
7	Burnt stone slabs dressed	S. ft.	1,739
8	Cut stone cornice	R. ft.	368
9	Dressing the faces of masonry	S. ft.	3,925
10	Surki mortar pointing	Sq.	67·00
11	Providing guard stones	No.	6
12	Do date guard stones	"	2
13	Rough stone suji cut apron	C. yd.	214
14	Bailing charges	L. S.	...
15	Divertion of the road way	L. S.	...
16	Dismantling masonary and other sundry works	L. S.	...
	Road way.		
17	Earthwork embankment	C. yd.	10,282
18	Turfing	Sq.	1·50
19	Collecting carting metal	C. yd.	214
20	Do gravel	"	26
21	Spreading and consolidating metal	"	214
22	Do do gravel	"	26
23	Collecting and spreading sand	"	5
24	Constructing dry stone parapet	"	167

A. PUTTUSAMAIYA,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

BANGALORE CITY MUNICIPALITY.

Notice.

Notice is hereby given that sealed tenders will be received at the office of the Honorary President, City Municipality, Bangalore, for watering the roads in the City for the months of February, March and April 1919 up to 10th February 1919.

1. Each tenderer must definitely state for what amount he can water each road by carting water from tanks.

2. The roads should be watered to 5 yards width.

3. The watering should be commenced at 4 A.M. and completed by 7 A.M. each day.

4. Each tenderer must be accompanied by a deposit of Rs. 20 in cash or currency notes as earnest money and be superscribed "Tender for watering roads."